




Status of the Vacuum System of the TTF-Linac

Kirsten Zapfe, DESY Hamburg

TESLA-Collaboration Meeting, Nov. 8-10, 1999

Content


- **Overview**
- **Cleaning and Installation Procedures**
- **Running Experience**
- **Summary and Outlook**



Overview



About 120 m of beam pipe



● Cold system (2 K) with isolation vacuum and separate warm coupler vacuum

- Capture cavity
- Cryo modules ACC1 and ACC2

● Warm beam pipe

- RF-gun
- Sectors 400 (bunch compressor I) - 600
- Bunch compressor II
- ACC3 (temporary beam line)
- Collimator
- Undulator
- Experimental area incl. FEL diagnostic





● Pumping and pressure readout

- > 30 ion getter pumps (60 l/s)
 - ➔ also used for pressure read out (min. $3 \cdot 10^{-11}$ mbar)
- > 30 titanium sublimation pumps (1000 l/s)

● Segmentation


- 12 all metal gate valves
 - valves automatically closed if
 - ➔ pressure $p > 10^{-7}$ mbar
 - ➔ cryo ok missing
 - ➔ failure of compressed air
- 2 fast shutters downstream of second module
 - ➔ trigger signal from additional small ion getter pumps with fast readout (undulator, FEL diagnostic)
 - ➔ total closing time of ≈ 20 ms corresponds to distance of 20 m


● Control system

- all vacuum equipment (pumps, valves, pump stations, ...) integrated into TTF-control system



Section of the Temporary Beam Line







Cleaning and Installation Procedures

Goal:

**minimize risk of particle/gas contamination of
s.c. cavities from other vacuum components**

● Careful cleaning of all vacuum components

- vacuum firing at 950 °C (2 h)
 - ➔ reduce outgassing of H₂
- cleaning of all vacuum components in clean room
 - ultrasonic bath
 - rinsing with ultra pure water
 - drying in class 10-100
 - pumping with high gas flow (“pump and purge”) **time consuming!**
 - assembly of diagnostic elements in clean room
 - ➔ careful planning with other clean room activities

⌚ Installation in linac using local clean rooms


- movable clean rooms
- filter elements for variable geometry

⌚ Special pump down/venting procedures

- movable oilfree pump stations for pump down
- laminar gas flow directed away from cavities
 - ➔ slower than standard procedures
- ultra clean gas for venting




Set up used for venting



➔ pump and purge vent line several times before venting

venting of beam line segment






Running Experience

● Overall performance

- low pressure ($<10^{-10}$ mbar) in most areas



Nov. 4, 10:30 am

- low gas load
 - ➔ activation of titanium sublimation pumps every few weeks
- 3 leaks in present system known
 - ➔ beam vacuum - isolation vacuum ACC2 (module 2)
 - ➔ Helium line - isolation vacuum ACC1 (module 3)
 - ➔ toroid in exp. station 5 (ceramics)

○ Safety system



- several times closing of gate valves due to strong pressure rise
- fast shutters not yet activated by vacuum problems





● Injector


- installation of RF injector in autumn 98
 - ➔ FERMILAB gun
 - ➔ cathode exchange system (INFN Milano)
 - ➔ “quick” exchange of FERMILAB and DESY gun possible
- Cs₂Te cathodes should never see bad vacuum (H₂O, O₂)
 - ➔ preparation of cathodes under vacuum in Milano
 - ➔ transport to DESY in special vacuum chamber with ion getter pump
 - (penning power supply connected to car battery)
 - ➔ connection to loading chamber at DESY under vacuum
- some vacuum activities during exchange of cathodes
- slow degradation of gun vacuum during beam operation



Cathode System

INFN Milano LASA
DESY (Vacuum equ.)

- Cs₂Te cathode: high QE (>1 % over months)
- The cathode system allows to change the cathode without breaking the vacuum
This is essential to maintain the high quantum efficiency of the Cs₂Te cathode



- The cathodes are prepared off side



● Sector 400-600

- ➔ vacuum system originally built and installed by Orsay
- most parts of sector 400 exchanged by bunch compressor I and diagnostic for RF-injector
- several monitors improved, changed or added
- original ion getter pumps (read out limited to 10^{-9} mbar) exchanged by standard pump combination (GP+TSP)
 - ➔ improvement of pumping speed and pressure read out

● Bunch compressor II

- installed in autumn 98
- dipole chambers with 17 mm gap height
- future plans
 - ➔ installation of dipole chamber with 8 mm gap height
 - ➔ installation of RAFEL experiment in straight section

● ACC3

- still temporary beamline
 - ➔ space for additional experiments, e.g. feedback kicker


● Collimator section

- 2 spoiler ($\Phi = 6$ mm, several cm long), 3 absorbers
 - ➔ necessary for protection of undulator vacuum chamber
- high filling factor with spoilers, absorbers, magnets and monitors
- exact positioning of components critical
 - ➔ many difficulties to align components correctly




37.320

27.300,3



37.687.0






27.239

top view

STAND: 16.11.1998


Project	DESY-MVPI	Sheet No.	0 97 5670/0.003
Task	Bunchcompressor II	Scale	1:1
Author		Date	
Checked		Drawn	
Approved		Material	



Pos.	Benennung
1	Pumpe 1
1a	Vorwärmstück 1
2	Vorwärmstück 2
3	Füllstandsperch L=100
4	Bohrung
5	Reinigt. BH
6	Füllstandsperch L=147,5
7	Pumpe 2
7a	Vorwärmstück 2
8	Spüler 1
9	Korrektormagnet 1
9a	Untergerüst 1

Pos.	Benennung
9c	Untergerüst 1
10a	Pumpe 3
10b	Vorwärmstück 3
11	Bohrung experiment
12	OH-Schirm
13a	Pumpe 4
13b	Vorwärmstück 4
14	Korrektormagnet L=247,5
15	Reinigt. BH
16a	Korrektormagnet 2
16b	Untergerüst 2

Pos.	Benennung
18	Spüler 2
19a	Pumpe 5
19b	Vorwärmstück 5
20	Assorier 2
21	Vorwärmstück 6
22	Füllstandsperch L=50
23	Assorier 3
24	Winkeluntergerüst
25	Rohr-Steue
26	Laserspitzenstrahl



Rev.	Benennung	Datum
5.0		07.12.99
3.0		10.12.99
2.0		02.12.99

Rev.	Benennung	Datum
1.0		
2.0		
3.0		
4.0		
5.0		
6.0		
7.0		
8.0		
9.0		
10.0		
11.0		
12.0		
13.0		
14.0		
15.0		
16.0		
17.0		
18.0		
19.0		
20.0		
21.0		
22.0		
23.0		
24.0		
25.0		
26.0		
27.0		
28.0		
29.0		
30.0		

Rev.	Benennung	Datum
1.0		
2.0		
3.0		
4.0		
5.0		
6.0		
7.0		
8.0		
9.0		
10.0		
11.0		
12.0		
13.0		
14.0		
15.0		
16.0		
17.0		
18.0		
19.0		
20.0		
21.0		
22.0		
23.0		
24.0		
25.0		
26.0		
27.0		
28.0		
29.0		
30.0		

Festpunkte Revision Datum
 TTP-FEL
 Kollimatorstrahl
 DESY-FOET
 0 98 8401/0.000 1:



● Undulator section

- difficult connections between undulator chambers and monitor blocks (space)
- pressure limited to $\approx 5 \cdot 10^{-9}$ mbar due to long, narrow beam pipe ($\Phi = 9.5$ mm, 4.5 m distance of pumps)

● Experimental area

- FEL-diagnostic installed in straight section
- little free space left
- future installations
 - ➔ wake-field experiment
 - ➔ beam-trajectory-monitor

● Cold beam vacuum

- leaks in module 1 and 2

● Isolation vacuum

- one pump station/module running permanently

● Warm coupler vacuum

- 1 ion getter pump + titanium sublimation pump/module
- many vacuum bursts during conditioning
 - ➔ time limiting factor
 - ➔ substantial improvements needed





Summary and Outlook

- **Vacuum system working reliable**
- **Leak in Modules need to be fixed in future**
- **No major vacuum break downs**
- **Space for new components very limited**
- *Improvement of injector vac. system*
- **Installations during next shut-down**
 - dipol chamber with smaller gap height
 - RAFEL-Experiment (BC II, FEL-diagnostics)
 - feedback kicker (experimental area)
 - wake-field experiment/beam-trajectory-monitor (behind undulator)

