


150 kW Power Plant for the ELETTRA RF System Upgrade

***Alessandro Fabris
On behalf of the ELETTRA RF group***



4th CW And High Average Power RF Workshop
Argonne, Illinois, USA. May 1-4, 2006
ELETTRA RF UPGRADE - A. Fabris


Overview / Power Plant / Status / Summary

- **ELETTRA is the Italian third generation light source in operation since October 1993 in Trieste.**
- The machine operates roughly 6500 hours/year, providing more than 5000 hours of light to the users.
- Operating modes:
 - Injection energy **0.9 GeV (linac injector)**
 - Multibunch (90% contiguous): **2 GeV, 330 mA**
 - Multibunch (90% contiguous): **2.4 GeV, 150 mA**
 - 4 bunches: **2 GeV, 40 mA**
 - SR FEL: **0.75-0.9 GeV, 40 mA (4 bunches)**
- New Major upgrades of the laboratory:
 - Replacement of the linac with a full energy **booster** injector
 - **FERMI**, FEL facility based on the upgrade of the existing linac
- Major upgrades of the storage ring:
 - RF Upgrade
 - Global Orbit Feedback
 -



Overview / Power Plant / Status / Summary

- The RF system did not have any major upgrade from its installation in 1993.
- It was designed for 400 mA, 1.5 GeV.
- It is composed of four 500 MHz 60 kW plants, using a UHF TV klystron as the main amplifying stage.
- Each plant feeds an ELETTRA type cavity.
- The requirements of RF power have greatly increased with the number of installed insertion devices.



Overview / Power Plant / Status / Summary

➤ TARGET OF THE PROJECT

- Provide the RF system with the necessary **operating margins**, when all IDs are operational (with a slight improvement also in beam lifetime).
- Increase available RF power in view of possible increase of beam current and energy.

➤ DESIGN STRATEGY


- **Minimum interference** with machine operation.
 - Gradual approach.
 - No increase of the space for RF components in the machine.
 - Same number of cavities.
 - No sc cavities.
- **Consistency** with other upgrades of the facility.
- **Take benefit of working in the UHF band.**
 - Use as much as possible solutions adopted in broadcast applications.



Overview / Power Plant / Status / Summary

➤MULTI-STAGE APPROACH


- PHASE A:** upgrade one 60 kW plant to 150 kW
- PHASE B:** repeat phase A on another plant
- PHASE C:** upgrade the two remaining plants in the same way
- At the end of phase C, the available RF power will be **600 kW**.




PHASE A IS NOW IN THE CONSTRUCTION PHASE



Overview / Power Plant / Status / Summary



➤ Available beam power (in kW)




➤ Touschek lifetime (hours) at the usual currents and energies (3HC not taken into account).



Power Plant : Amplifier/ Power Transmission / Layout

- The Power Amplifier will be made **combining two 80 kW** transmitters providing 150 kW at the amplifier output.
- The final stage of each transmitter will be a 80 kW IOT.
- The output of the two transmitters will be combined by means of a **switchless combiner**.
- Each transmitter will be completely independent to allow standalone operation, thus increasing operational flexibility.** The fault or the maintenance of one transmitter does not imply the interruption of the operation of the plant, since the other transmitter continues to operate.
- It has been acquired as a **turn-key system from industry (ELECTROSYS, Orvieto Italy).**




Power Plant : **Amplifier** / Power Transmission / Layout

Power Amplifier - Abridged specifications	
Operating frequency	499.654 MHz
Bandwidth (-1dB)	± 1 MHz
Output power higher than	150 kW cw
Input power	13 dBm
Max. admissible VSWR(all phases)	1.3
Output power dynamics	> 35 dB
Harmonic content at output power	< -30 dBc
Spurious and sidebands levels in ± 20 MHz	< -60 dBc
Signal to noise ratio within bandwidth	better than 70 dBc
Efficiency at full output power	> 65 %
Maximum RF phase variation vs. output power for full drive modulation	30° overall
Power stability	$\pm 1\%$ at each output level
Phase stability	$\pm 0.5^\circ$ at each output level




Power Plant : **Amplifier** / Power Transmission / Layout



Single transmitter block diagram



Power Plant : Amplifier/ Power Transmission / Layout



Courtesy of Electrosys



Power Plant : **Amplifier** / Power Transmission / Layout






Pictures taken at Electrosys



Power Plant : Amplifier / Power Transmission / Layout

- ›The tube adopted is Thales TH 793.
- ›The use of other tubes assemblies could eventually be possible by use of a replacement kit.



. C.W. output power	80 kW
. Beam voltage	36 kV
. Beam current	3.3 A
. Body current	50 mA
. Quiescent beam current	0.15 A
. Filament current	24 A
. Focusing current	18 A
. Grid voltage	-95 V
. Grid current	-60mA
. Efficiency	67 %
. Gain	22.7 dB
. Bandwidth at - 1 dB	6.5 MHz
. Frequency	500 MHz

Courtesy of
THALES ELECTRON DEVICES



Power Plant : **Amplifier** / Power Transmission / Layout

➤ IOT POWER SUPPLIES


➤ The specifications allow for some redundancy to take some margins in case of different tubes

Typical specifications for one tube	
Power	80 kW
High Voltage Supply	37 kV, 3.8 A
Heater Supply	12 V, 40 A
Ion Pump supply	4 kV, 3 mA
Grid supply	-150 V, \pm 130 mA
Focus Supply	12 V, 30 A



Power Plant : **Amplifier** / Power Transmission / Layout

- ›The HV power supply of each IOT will be a **switched mode power supply**.
 - ›The structure is **more compact**.
 - ›Lower residual ripple.
 - ›Beam voltage is stabilised independently of:
 - ›Output power variations.
 - ›Mains input variations
 - ›If needed, **switching frequency can be adjusted** in the range 16 to 21 kHz.
 - ›No oil capacitors or transformers are used.
 - ›No crowbar tube.



Power Plant : **Amplifier** / Power Transmission / Layout

➤ **SWITCHLESS COMBINER**

- Four ports device made up from two hybrids and a variable phase shifter.
- Depending on the phase shifter position one has four modes of operation.

➤ Advantages:

- 3 dB power loss when one transmitter is out of service
- Maintenance of one transmitter can be made while the other is in service
- Hot adjustment is possible

➤ Disadvantages:

- Dimensions



Pictures taken at Electrosys



Power Plant : **Amplifier** / Power Transmission / Layout



Power Plant : **Amplifier** / Power Transmission / Layout



Pictures taken at Electrosys




Power Plant : Amplifier/ Power Transmission / Layout

- ›The power amplifier will be protected by a 200 kW 500 MHz circulator, which has been ordered to AFT (Germany)
- ›Power transmission will be done with WR1800 waveguides. The waveguide components have been ordered to MEGA Industries (USA)




Power Plant : Amplifier/ Power Transmission / **Layout**



Power Plant : Amplifier/ Power Transmission / Layout



Overview / Power Plant / **Status** / Summary




►The new cavity was installed in section 9 in **November 2003**. It is similar to the ones provided to SLS and ANKA (upgraded cooling efficiency).

►In parallel a design study is in course to improve the performances of the power coupler both at fundamental and HOM frequencies.

►This includes:

►Design of a **new coaxial transition element** (airside) integrated with the **coaxial to waveguide transition**.

►Installation of **diagnostic devices** in the coaxial element.



➤ **Components**

➤ Amplifier:

- Factory acceptance test to be completed next week.
- Afterwards delivered to Trieste.

➤ Power Transmission:

- Circulator to be delivered these days.
- Waveguides to be delivered first half of June.

➤ **Installations**

➤ Installations have to fit in the planned shutdown, therefore they should be well organised.

➤ Program of activities:

- Summer shutdown (from end May to half July 2006): amplifier and circulator installation.
- End July to October 2006: plant commissioning on dummy load.
- October' s shutdown (3 weeks): connection to the cavity.
- November-December 2006: new plant commissioning.
- January 2007: start dismantling old 60 kW plant.



Overview / Power Plant / Status / **Summary**

➤ **The first phase (phase A) of the ELETTRA RF Upgrade is under construction.**

➤ A multi stage approach was chosen to minimise interference.

➤ Most of the components take benefit of existing products in UHF broadcast market and are supplied by industries.

➤ The completion of phase A is foreseen by the end of this year.

➤ This phase will provide a certain amount of safety margin to the system and provide the booster power plant (to be installed in 2007).

➤ Based on the results and on the development activities of the lab, a decision on the timing of the remaining phases will be taken.



► **ACKNOWLEDGEMENTS**

► Many thanks to:

- G. Ocera from ELECTROSYS and his staff.
- The ELETTRA RF Group: C. Pasotti, M. Rinaldi, M. Bocciai.

