

# Fourth CW and High Average Power RF Workshop - 2006

## The Spallation Neutron Source Accumulator Ring RF System

T. Hardek, M. Piller, M. Champion, M. Crofford (ORNL)




A. Zaltsman, K Smith (BNL)



# First Beam On Target

## SNS Channel 4

Last Update: 4/28/2006 2:13:33 PM






Protons	53.8G	Goal 10T
Total Protons	331G	
Charge (C)	8.62n	
1-eV Moderator Coupling (n/ster/eV/p)	239u	
PEP-Specified Neutronics Units (n/ster/p)	4.60m	Goal 5m

# 1.2e13 Protons On Target

## SNS Channel 4

Last Update: 4/28/2006 3:30:13 PM



Protons	12.6T	Goal 10T
Total Protons	201T	
Charge (C)	2.01u	
1-eV Moderator Coupling (n/ster/eV/p)	1.57u	
PEP-Specified Neutronics Units (n/ster/p)	30.2u	5m Achieved

# Overview

- **List of Participants**
- **General SNS Machine Background**
- **Accumulator Ring RF System Details**
- **Present Status**
- **Some current operational results**
- **Conclusions**

# Brookhaven and Original ORNL Staff

## BNL

Alex Zaltsman	Project Manager
Kevin Smith	LLRF Engineer
Mike Blaskiewicz	Physics
John Butler	PLC Engineer
Freddy Severino	Analog/LabView Controls
Pablo Rosas	HV Supplies

## ORNL

Tom Owens	RF Engineer
Brian Gross	RF Technician
John Reed	Low Level Controls

# Present ORNL Support

**Tom Hardek**

**Lead RF Engineer**

**Maurice Piller**

**LLRF Engineer**

**Mark Crofford**

**LLRF Engineer**

**Mike Clemmer**

**Lead RF Technician**

**Dale Heidenreich**

**RF Technician**

**John De Baca**

**RF Technician**

**Mark Cardinal**

**RF Technician**

**Rob Peglow**

**RF Technician**

**Robert Wilson**

**RF Technician**

**Pam Gurd**

**High Level RF EPICS Controls**

**Kay-Uwe Kasemir**

**LLRF EPICS Controls**

**Xiaosong Geng**

**PLC & EPICS Controls**



**OAK RIDGE NATIONAL LABORATORY**  
**U. S. DEPARTMENT OF ENERGY**



# SNS Facility – Artists View



# Site Photo - 2005




**OAK RIDGE NATIONAL LABORATORY**  
**U. S. DEPARTMENT OF ENERGY**








# Overall Site Layout




# Layout of Linac RF Modules

	402.5 MHz, 2.5 MW klystron	3 Transmitter	3 Modulators
	805 MHz, 5 MW klystron	4 Transmitter	4 Modulators
	805 MHz, 0.55 MW klystron	16 Transmitter	8 Modulators




# Accumulator Ring Parameters

- **Circum** 248 m
- **Energy** 1 GeV
- **frev** 1 MHz
- **Qx, Qy** 6.23, 6.20
- **$\xi_x, \xi_y$**  -7.9, -6.9
- **Accum turns** 1060
- **Final Intensity**  $1.5 \times 10^{14}$
- **Peak Current** 52 A
- **RF Volts (h=1)** 40 kV
- **(h=2)** 20 kV
- **Injected Pulse** 645 ns
- **Injected Gap** 300 ns
- **Extracted Pulse** 695 ns
- **Extracted Gap** 250 ns



# RF System Parameters

- 4 Cavities – Two Gaps per Cavity
- 3 Fundamental Revolution Frequency Cavities – 7 kV per Gap
- 1 Second Harmonic Cavity – 10 kV per Gap
- Each Cavity has one Final Amplifier
- The System must handle 52 amperes peak beam current
- Beam Loading Compensation – Cavity Tuning, Feed Forward
- Single Turn Delay RF Feedback is possible but will take some development.



# First RF Station at ORNL – April 2004



# Amplifiers and Cavities installed in Ring

RF21

RF13

RF12

RF11



# Final Amplifier – THALES TH558



# Station RF21 in Ring Service Building



Filament Supply


Anode Power Supply  
Rack

Anode Capacitor Bank

Cavity Tuning Supply




# DC Bias and RF Currents in the Cavity



# Cavity Internal View

**Amplifier Coupling Loop**

**Gap Capacitors**




**Ferrite Housing**

**Gap Connecting Buss**

- Drive loop is a wire that passes through a tube welded to the beam pipe.
- Gaps are connected by heavy straps.
- Ferrite housing and Beam pipe form the bias winding

# Cavity Resonance Curves




- Note that the higher voltage resonance curves are really skewed

- We are probably pushing the ferrite too hard.

- Amplitude feedback loop will be difficult.

# Dynamic Tuning Supply

- System design requires a 450 ampere 180 Hz sinusoidal current swing from the Cavity Dynamic Tuning Supply to help compensate for beam loading.
- Excessive connecting lead inductance could require higher voltages than available from the supply.
- We measure 25.5 uHy. - Well within the supply range.
- Supply capable of -18 Volts to +24 Volts.



# Ring RF Control Room

High Level RF Control Racks

LLRF Analog Modules

LLRF VME Boards



# Present Operational Status

- **The system is fully operational**
- **We have stored  $5e13$  Protons**
- **The Slow Feedback system had trouble holding  $5e13$  protons but we have not spent much time adjusting the system (*one 4 hour shift*)**
- **We have not tried Cavity Dynamic Tuning**
- **The Feed-Forward system included in the original design is under development**

# Ideal RF Waveform and Calculated Bunch Shape




Fig. 5.8.1: Simulation results for SNS just before extraction including beam loading for  $h = 1$  with one turn delay feedback. Parameters are described in the text and Table 5.8-2.

$V_0$  = Ideal RF Voltage

$V_g - V_0$  = Actual RF Voltage - Ideal RF Voltage


$V_{sc}$  = Space Charge Induced Voltage

$V_r$  = Voltage Due To Parasitic Resistance

$I$  = Beam Current


- 2<sup>nd</sup> harmonic is added to reduce the peak beam current.
- For low intensity beam cycles the 2<sup>nd</sup> harmonic cavity is not needed.

# 4e13 Protons - Nicely Bunched, No 2<sup>nd</sup> Harmonic






# 5e13 Protons - Present RF Limit



# Low Level System Screen



# Conclusions

- **Final Amplifiers are capable of supplying the current needed to compensate for beam loading**
- **Cavity Dynamic Tuning will be necessary**
- **With some adjustment the slow analog feedback along with Cavity Dynamic Tuning should allow us to reach design intensity.**
- **A Feed-Forward system that records a beam current sample and feeds it to the amplifier to counter beam current will be necessary for higher intensities.**