



**Argonne**  
NATIONAL  
LABORATORY

*... for a brighter future*



U.S. Department  
of Energy

UChicago ►  
Argonne<sub>LLC</sub>



A U.S. Department of Energy laboratory  
managed by UChicago Argonne, LLC


## ***SRF R&D for ERL***

***Ali Nassiri***

***Accelerator Systems Division***

***Advanced Photon Source***

***ESRF, Spring8, APS Three-Way Meeting (3WM08)***



## Key R&D

- Achieving very high intrinsic  $Q_0$  value
- Effective suppression of HOM
- Microphonics and optimal external  $Q_e$
- Fundamental power coupler for the Injector linac
- Dedicated Test Facility

# Design Parameters Comparison

|                               | ILC <sup>1</sup>                        | Light Source ERL <sup>2</sup>                |      |
|-------------------------------|---|--|------|
| Beam Energy                   | 500<br>COM                              | 5 – 8  | GeV  |
| Average beam Current          | 9.0                                     | 100  | mA   |
| Bunch train repetition rate   | 5                                       | $1.3 \times 10^9$                            | Hz   |
| RF duty factor                | $7.5 \times 10^{-3} - 1 \times 10^{-2}$ | CW   |      |
| Average accelerating gradient | 31.5                                    | 20   | MV/m |
| Cavity Quality factor         | $1 \times 10^{10}$                      | $> 5 \times 10^{10}$<br>$(1 \times 10^{11})$ |      |
| Beam pulse length             | $9.5 \times 10^{-4}$                    | $2 \times 10^{-12}$                          | sec  |
| Total AC power consumption    | ~230                                    | ~ 50   | MW   |

<sup>1</sup> Barry Barish, GDE/ACFA Closing Beijing 7/02/07

<sup>2</sup> Ali Nassiri, APS MAC, Nov. 15-16,2006

# SRF requirements


- 7 GeV single pass cw linac
- 400 multi-cell SRF cavities for main linac
- Roughly 400 meter of rf linac
- 10 MeV, 100 mA Injector linac ( 1 MW RF power)
- Roughly 45 kW total losses ( dynamic and static losses) at 2<sup>0</sup>K
  - Large complex
  - Extremely heavy cryogenic load
- Robust and reliable power couplers (FPC) and HOM dampers
- Complex low-level rf control for amplitude, phase stability and microphonics
- Acceptable RF systems reliability and availability for beam up time

# High(er) $Q_0$

## ■ Material Science for higher Q

- $10^{10}$  is O.K.,  $5 \times 10^{10}$  is better, but  $10^{11}$  is great
- Refine surface processing
- Large crystal
- Single crystal

$$P_{\text{refrigeration}} \propto 1/Q_0$$




Single-cell 1.3 GHz cavity tested at 1.6K at Saclay

# High(er) $Q_0$ (2)



## Alternative materials

- Nb<sub>3</sub>Sn
- NbN
- MgB<sub>2</sub>
- YBCO
- Stronger reduction of BCS resistance because of use SC layer with higher  $\Delta$
- Nb<sub>3</sub>Sn thin film coating may triple the breakdown field of Nb and increase Q by 3-10 times\*



$$Q \sim \exp\left(\frac{\Delta}{K_B T}\right)$$



$$\Delta_{Nb_3Sn} \approx 1.8 \Delta_{Nb}$$



\*A. Gurevich, App. Phys. Lett. 88, 012511 (2006)

# Optimal Temperature


- Effect of residual resistance on AC power consumption ( non-BCS surface resistance)\*



\* Temperature dependent of Carnot efficiency of the cryoplant is included.

# HOM Suppression

- Multi-cell cavities with a larger number of cells would also improve linac packing factor, i.e., ratio of active length to total length
- This will reduce the cost of the ERL linac, BUT
- Strong HOM damping is essential with higher beam current which favors smaller number of cells




$$Q_b = 77 \text{ pC}$$

$$\kappa_{||} = 10 \text{ V/pC}$$

$$f_{bunch} = 1300 \text{ MHz (int erbunch spacing 770 ps)}$$

$$P_{HOM} = 150 \text{ W (per cavity for two beams)}$$


- HOM power dissipation at room temperature
- High-current optimized cell shape for good rf efficiency
- Cell Shape to have good HOM frequency spectrum





# Microphonics and External Q

- Cavity and cryostat should be designed for low microphonics
- Higher  $Q_{\text{ext}}$   $\longrightarrow$  less power is needed
- Detuning  $\longrightarrow$  more power is needed especially for large Q



$$Q_{L,\text{optimal}} = \frac{1}{2} \frac{f_0}{\Delta f}$$

$$P_{g,\text{minimal}} = \frac{V_{\text{acc}}^2}{2R/Q} \frac{\Delta f}{f_0}$$

## RF Control:

- Operating at very high Q,  $\sim 10^8$  (100 mA beam)
- Amplitude and phase fluctuation specs:  
 $10^{-4}$ ,  $0.03^\circ$  or better

- For 10 Hz detuning ( $< 20$  Hz peak):  $Q_e = 7 \times 10^7$
- This minimizes average power but not the max power that needs to be available.

# FPC for the Injector Linac

## ■ Power Coupler

- No significant issue for the main linac
- High power injector linac coupler needs to be developed
  - *Power handling > 150 kW cw*
  - *Variable coupling factor*

## ■ Energy gain 5 to 15 MeV

## ■ High cw current:

- 100 mA ( 77 pC/bunch) @ 5MV, 500 kW,  $\varepsilon \sim 1$  mm-mrad
- 100 mA (77 pC/bunch) @ 10 MV, 1000 kW,  $\varepsilon \sim 1$  mm-mrad
- 33 mA (26 pC/bunch) @ 15 MV, 500 kW,  $\varepsilon \sim 0.1$  mm-mrad

## ■ 1.4 GHz SRF 2-cell cavities:

- Gradient  $\sim 15$  MV/m (  $\sim 3$  MV)
- Need three 2-cell cavities
- Two couplers/ cavity ( Kick cancellation by symmetry)
- FPCs need to be designed to handle power on the order of 150 kW or more

## *A Need for a Dedicated Test Facility*

- There is a definite need for a beam test facility to test and characterize components of a the full-size APS ERL
- This can be accomplished with a moderate electron beam energy (  $\sim 200$  MeV) and a low average current (  $\sim 10$  mA)
- The purpose of such facility is to characterize and understand issues such as:
  - Electron source
  - Injection scheme
  - Merger
  - Beam transport at injection energy
  - Ultra-low emittance beams generation and preservation
  - Power handling capabilities of the injector linac ( FPC performance)
  - System integration
  - Experience with SRF operation
  - Operational reliability